



BID FORM (BILL OF QUANTITIES)

NAME OF THE PROJECT : **Proposed Construction of Three (3) Storey University Health Center**

APPROVED BUDGET OF CONTRACT : **TWELVE MILLION FIVE HUNDRED THIRTY-FOUR THOUSAND AND 00/100 (P12,534,000.00) ONLY**

BRIEF DESCRIPTION : **Construction of Three (3) Storey University Health Center**

SOURCE OF FUND : **GoP CY 2021**

CONTRACT DURATION : **Two Hundred Forty (240) calendar days**

ITEM NO.	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL COST
A. GENERAL REQUIREMENTS					
B.7	Occupational Safety and Health	1.00	l.s.	P	P
B.5	Project Billboard	2.00	each	P	P
B.9	Mobilization and Demobilization (including G.I. Sheet Rib - Type Board - Up)	1.00	l.s.	P	P
B.3	Permits and Clearances (including Legworks Payments, Processing, Signing, Sealing and Designing Analysis)	1.00	l.s.	P	P
B. EARTHWORKS					
803(1)a	Structure Excavation (common soil)	870.80	cu.m.	P	P
804(1)a	Embankment from Structure Excavation	653.10	cu.m.	P	P
101(6)	Removal of Existing Structure and Obstruction	1.00	l.s.	P	P
100(2)b	Individual Removal of Trees	2.00	each	P	P
1000(1)	Soil Poisoning	26.00	Liters	P	P
804(1)b	Embankment from Common Borrow by Equipment	328.70	cu.m.	P	P
C. STRUCTURAL WORKS					
900(1)a1	Structural Concrete, Class A	374.95	cu.m.	P	P
901(1)	Lean Concrete	40.00	cu.m.	P	P

902(1)b	Reinforcing Steel of Reinforced Concrete Structures (Deformed, Grade 40)	44,250.00	kgs	P	P
903(2)	Formworks and Falseworks	1,466.57	sq.m.	P	P
D. ARCHITECTURAL WORKS					
1046	100mm CHB Non Load Bearing/Load Bearing (including Reinforcing Steel)	345.85	sq.m.	P	P



1046(2)	150mm CHB Non Load Bearing/Load Bearing (including Reinforcing Steel)	225.40	sq.m.	P	P
1027	Cement Plaster Finish 1/2"thk Plain cement plastering both faces	1,142.00	sq.m.	P	P
1003(1)a1	Ceiling (4.5mm thick Fiber Cement on Metal Frames)	21.80	sq.m.	P	P
1016(1)b	Liquid Water Proofing (GF Toilets and 2F Slab)	343.10	sq.m.	P	P
1018(2)	Non-skid vitrified Tiles 60x60cm	85.20	sq.m.	P	P
1021(1)b	Smooth Cement troweled Finish	457.15	sq.m.	P	P
1032(1)d	Ceiling Painting Works (Fibercement Board and Slab Soffit)	300.60	sq.m.	P	P
1010(2)b	Wooden Panel Door with complete accessories and frames-Automotive Paint	91.00	sq.m.	P	P
1042(2)	Steel Doors	9.30	sq.m.	P	P
1003(2)f	Door Aluminum Threshold	6.30	l.m	P	P
1012(4)a2	Tempered Glass Doors	12.96	sq.m.	P	P
1002(28)	Toilet bath shower curtain(mold and water proof with complete accessories)	1.00	l.s	P	P
1032(1)a	Masonry Painting Works (interior and exterior)	1,142.00	sq.m.	P	P
1012(7)	Glass and Glazing	95.72	sq.m.	P	P

E. ELECTRICAL WORKS

1101(1)a	3.5mm2 - 5.5mm2 Electric Wire (THHN color coding)	1,700.00	m	P	P
1101(21)	Simplex/Duplex Universal Convenience Outlet, Duplex Universal Floor Recessed Convenience Outlet, Duplex Universal Weatherproof Convenience Outlet	63.00	pcs	P	P
1102(1)d	Panel Boards with Main Breaker/Branches, DPB NEMA 3 Main: 500AT, 3P, 220V	1.00	set	P	P
1102(1)c	Main Circuit Breaker (MCB) NEMA 4x, Main: 600AT, 3P, 220V	1.00	set	P	P
1101(33)	Switches	28.00	pcs	P	P
1102 (1)a	Panel Boards with Main Breaker/Branches, PB1 NEMA 3 Main: 100AT, 3P, 220V	1.00	set	P	P

Handwritten signature

1103 (1)	Lighting Fixtures (including Emergency and Exit Lights)	106.00	pcs	P	P
1101(1)f	250mm2 Electric Wire (THHN)	24.00	m	P	P
1101(1)e	125mm2 Electric Wire (THHN)	60.00	m	P	P
1101(1)c	30.0mm2, 38.0mm2, 80.0mm2 Electric Wire (THHN)	48.00	m	P	P
1101(1)d	50mmØ,63mmØ,90mmØ Polyvinyl Chloride (PVC) Pipes	6.00	length	P	P
1102 (1)b	Panel Boards with Main Breaker/Branches, PB2 NEMA 3 Main: 200AT, 3P, 220V	1.00	set	P	P
1101(1)b	8.0mm2-14.0mm2 - 22.0mm2 Electric Wire (THW) Wire	37.00	m	P	P
1100(6)	20mmØ Polyvinyl Chloride (PVC) Pipes	214.00	length	P	P
1100(9)	PVC/RSC/IMC/EMT Conduit Fittings including Junction Box/Pull Box/Utility Box/Square Box	1.00	l.s.	P	P
1109(4)	30mm2 Bare Copper Wire	10.00	m	P	P
1109(5)	Grounding Rod	3.00	pcs	P	P
1100(1)a	Cable Tray	9.00	pcs	P	P

F. PLUMBING AND SANITARY WORKS

1002 (6)	Urinal with Complete Accessories	2.00	set	P	P
1002 (5)	Water Closet with Complete Accessories	3.00	set	P	P
1002 (14)	Wall Hung/Countertop/Under Counter LAVATORY with Complete Accessories	13.00	set	P	P
1002 (14)a	Kitchen Sink / Laundry Sink with Complete Accessories	4.00	set	P	P
1002 (16)	Floor Drain	3.00	set	P	P
1002 (17)	Floor Cleanout (Stainless Steel for Indoor Ground Floor)	5.00	set	P	P
1002(21)	Water Meter/Check Valve/Gate Valve/Float Valve	11.00	pcs	P	P
1002(23)	Air Admittance Valve (for Vent System)	1.00	pc	P	P
1002(2)a	25mmØ - 50mmØ Polypropylene Random Copolymer (PPR-C) Pipes, PN20	40.00	pcs	P	P
1002(2)b	Polypropylene Random Copolymer (PPR-C) Fittings - (all fittings necessary to complete the works to its intended purposes)	1.00	l.s.	P	P

Handwritten signature

1001 (1)a	32mmØ - 150mmØ PVC Pipe, Series 1000	163.00	m	P	P
1001 (1)b	PVC Fittings, Series 1000	1.00	l.s.	P	P
TOTAL					P

Total Bid Price in Figure: _____

Total Bid Price in Words: _____

Name and Signature of Bidder: _____

All bid proposals must be sealed in envelopes properly labeled and submitted to this University on or before the deadline of submission of bids, **October 18, 2021, 10:00 A.M.** at the Procurement Services, 2nd Level Gymnasium Lobby, University of Science and Technology of Southern Philippines, C.M. Recto Ave., Lapasan Cagayan de Oro City.

The University of Science and Technology of Southern Philippines assumes no responsibility whatsoever to compensate or indemnify bidders for any expenses incurred in the preparation of the bid. The USTsP neither assumes any obligation for whatsoever losses that the bidders may incur in the preparation on their bids nor guarantee that an award will be made.


ATTY. KENNETH M. KEMPIS
 BAC II Chairperson