OFFICE OF THE BIDS AND AWARDS COMMITTEE I

NAME OF PROCURING ENTITY	:	UNIVERSITY OF SCIENCE AND TECHNOLOGY OF SOUTHERN PHILIPPINES (USTP) – CDO CAMPUS
PROJECT NAME	:	PROPOSED CONTINUATION OF THE CONSTRUCTION OF EIGHT-STOREY STUDENT CENTER AND EDUCATION COMPLEX PHASE 1A AT USTP-CDO CAMPUS CY 2026
LOCATION	:	USTP- CAGAYAN DE ORO CAMPUS

MINIMUM REQUIREMENTS FOR CONSTRUCTION SAFETY AND HEALTH PROGRAM

A. Provision for adequate standard protective equipment. Workers with in the project site shall be required to wear the necessary and appropriate Personal Protective Equipment (PPE) at all times;

B. Workers who are working from unguarded surfaces six (6) meters or more above water or ground, temporary or permanent floor platform, scaffolds or where they are exposed to the possibility of falls hazardous to life or limb, must be provided with safety harnesses and life lines;

C. Workers must be provided with special protective equipment, such as specialized goggles or respirators for welders and painters or paint applicators; and

D. All other personnel who are either authorized or allowed to be at a construction site shall wear appropriate PPE.

E. Major Equipment shall have the latest safety accreditation.

F. Provision of Board-up.

G. Workers Ingress and Egress Program.

H. Provision of ID and Uniforms.

I. Provision of Temporary Facilities (Barracks, C.R., Laydown Area, Fabrication Area, etc.)