



# I. INTRODUCTION

The drawings and the Specification are complementary to each other. Drawings are graphic means of showing works to be done. They are particularly suited to showing where materials are located. Thus, drawing exists essentially to show sizes, location, and placement. Not all works, however, can be presented in the drawings. Generalized works are usually in statement form; hence the Contractor is strongly advised to read the specification carefully.

Specification on the other hand, is used to describe the materials, construction techniques, samples, shop drawings, guarantee, and the other contract requirements. Together, the Drawings and the Specification are used to inform the contractor. In cases where specified brand carries with it the manufacture's specifications, the manufacture's specification shall hold the precedence over this specification.

## II. THE LANGUAGE OF THE SPECIFICATIONS:

The specifications are the abbreviated type and include incomplete sentences. The selection of sentence structure depends on the underlying principles of the specifications:

a. That the technical specifications are only one part of the Contract Document.

b. That the contract is between the Owner and the General Contractor; and

c. That the General Contractor is the only party responsible for completing the work in accordance with the Contract Document

#### Therefore:

A. Only the General Contractor is referred to in the specification so as not to violate the intent of the contract and so as not to undermine the proper chain of command.

B. Any reference to Specialty Trade Contractors in the technical Specifications is made only in so far a selection of specialty Trade Contractors is made through bidding. Once the Specialty Trade Contractions are selected and assigned to the General Contractor, the General Contractor assumes all responsibilities for the execution of the whole project in accordance with the Contract Documents. Therefore, in the contract between the Owner and the General Contractor, the Specialty Trade Contractor, the Specialty Trade Contractor is not referred to the entire Contract Document, the work "Contractor" referred to the General Contractor.

C. The omission of the phrase "the contractor shall" is intentional because the whole specifications are directed to the Contractor. Omitted words or phrases shall be supplied by the interference in the same manner, as they are when a "note" occurs in the drawings.





D. Where "as shown", "as intended", "as detailed", or words similar import are used, it shall be understood that the reference in the drawings accompanying the specifications is made unless otherwise stated.

E. Where "as directed", "as required", "as permitted", "as authorized", "as approved", "as accepted", or other words similar import are used, it shall be understood that the direction, requirements, permission, authorization, approval, or acceptance of the Architect is intended unless otherwise stated.

F. As used herein, "provide" shall be understood to mean "provide complete in place" that is "furnished and installed".

# III. <u>GENERAL REQUIREMENTS:</u>

1. The contractor shall secure from the government agencies all necessary licenses and permits needed.

2. Cleanliness shall be maintained at all times within the job site and its immediate premises.

3. If errors or omissions appear in the drawings, specifications or other documents, these shall be referred to the designing architect.

4. The building site shall be filled up to the required grade.

5. All fills shall be in layers of 0.15m in thickness, each layer being thoroughly compacted by wetting and tamping.

6. All applicable provisions of the different divisions of the specification for each work trade shall apply for all items cited in this summary.

7. Materials deemed necessary to complete the work but not specifically mentioned in the specification, working drawings, of in the Contract Document, shall be supplied and installed by the Contractor without extra cost to the Owner. Such material shall be of the highest quality available and install and applied in a workmanlike manner at prescribed or appropriate locations.

8. Materials specifically mentioned in this Summary shall be installed following efficient and sound Engineering and Construction practice, and especially as per Manufacture's application and installation specification, which shall govern over all works, alluded in this Specification.

9. The Contractor shall clean the site and dispose waste after the completion of the project.

# IV. PREPARATION OF SITE:

- 1. The owner shall take out the building accurately and shall establish grades according to plans and specifications.
- 2. Basic batter board references as directed by the project engineer shall be erected at such places where they will not be disturbed during construction.





# V. <u>SPECIFICATION OUTLINE:</u>

# WORK ITEM PER DPWH STANDARD

# **CIVIL WORKS**

# EARTHWORKS

#### Item 803(1)a – Structure Excavation (Common Soil)

Referring to Item 103, Part C of volume II (Blue Book):

Description

This item shall consist of the necessary excavation for foundation of bridges, culverts, underdrains, and other structures not otherwise provided for in the Specifications. Except as otherwise provided for pipe culverts, the backfilling of completed structures and the disposal of all excavated surplus materials, shall be in accordance with these Specifications and in reasonable close with the Plans or as established by the Engineer.

This item shall include necessary diverting of live streams, bailing, pumping, draining, sheeting, bracing, and the necessary construction of cribs and cofferdams, and furnishing the materials therefore, and the subsequent removal of cribs and cofferdams and the placing of all necessary backfill.

It shall also include the furnishing and placing of approved foundation fill material to replace unsuitable material encountered below the foundation elevation of structures.

No allowance will be made for classification of different types of material encountered.

**Construction Requirements** 

Clearing and Grubbing

Prior to starting excavation operations in any area, all necessary clearing and grubbing in that area shall have been performed in accordance with Item 100 – Clearing and Grubbing.

Excavation

(1) General, all structures.

The Contractor shall notify the Engineer sufficiently in advance of the beginning of any excavation so that cross-sectional elevations and measurements may be taken on the undisturbed ground. The natural ground adjacent to the structure shall not be disturbed without permission of the Engineer.

Trenches or foundation pits for structures or structure footing shall be excavated to the lines and grades or elevations shown on the Plans or as staked y the Engineer. They shall be of sufficient size to permit the placing of structures or structure footings of the full width and length shown. The elevations of the bottoms of footings, as shown on the Plans, shall be considered as approximate only and the Engineer may order in writing, such changes in dimensions or elevations of footings as may be deemed necessary, to secure a satisfactory foundation.

Boulders, logs, and other objectionable materials encountered in excavation shall be removed.

After each excavation is completed, the Contractor shall notify the Engineer to that effect and no footing, bedding material or pipe culvert shall be placed until the Engineer has approved the depth of excavation and the character of the foundation material.

(2) Structures other than pipe culverts.

All rock or other hard foundation materials shall be cleaned of all loose materials, and cut to a firm surface, either level, stepped, or serrated as directed by the Engineer. All seams or crevices shall be





cleaned and grouted. All loose and disintegrated rocks and thin strata shal be removed. When the footing is to rest on material other than rock, excavation to final grade shall not be made until just before the footing is to be placed. When the foundation material is soft or mucky or otherwise unsuitable, as determined by the Engineer, the Contractor shall emove the unsuitable material and backfill with approved granular material. This foundation fill shall be placed and compacted in 150 mm. layers up to the foundation elevation.

When foundation piles are used, the excavation of each pit shall be completed before the piles are driven and any placing of foundation fill shall be done after the piles are driven. After the driving is completed, all loose and displaced materials shall be removed, leaving a smooth, solid bed to receive the footing.

#### Utilization of Excavated Materials

All excavated materials, so far as suitable, shall be utilized as backfill or embankment. The surplus materials shall be disposed off in such manner as not to obstruct the stream or otherwise impair the efficiency or appearance of the structure. No excavated materials shall e deposited at any time so as to endanger the partly finished structure.

Backfill and Embankment for Structures Other Than Pipe Culverts

Excavated areas around structures shall be backfilled with free draining granular material approved by the Engineer and placed in horizontal layers not over 150 mm. in thickness, to the level of the original ground surface. Each layer shall be moistened or dried as required and thoroughly compacted with mechanical tampers.

In placing backfills or embankment, the material shall be placed simultaneously in so far as possible to approximately the same elevation on both sides of an abutment, pier, or wall. If conditions require placing backfill or embankment appreciably higher on one side than on the opposite side, the additional material on the higher side shall not be placed until the masonry has been in place for 14 days, or until tests made by the laboratory under the supervision of the Engineer establishes that the masonry has attained sufficient strength to withstand any pressure created by the methods used and materials placed without damage or strain beyond a safe factor.

Backfill or embankment shall not be placed behind the walls of concrete culverts or abutments or rigid frame structures until the top slab is placed and cured. Backfill and embankment behind abutments held at the top y the superstructure, and behind the sidewalls of culverts, shall be carried up simultaneously behind opposite abutments or sidewalls.

All embankments adjacent to structures shall be constructed in horizontal layers and compacted (as prescribed in Subsection 104.3.3 – Compaction) except that mechanical tampers may be used for the required compaction. Special care shall be taken to prevent any wedging action against the structure, and slopes bounding or within the areas to be filled shall be benched or serrated to prevent wedge action. The placing of embankment and the benching of slopes shall continue in such a manner that at all times there will be horizontal berm of thoroughly compacted material for a distance at least equal to the height of the abutment or wall to be backfilled against except insofar as undisturbed material obtrudes upon the area.

Broken rock or coarse sand and gravel shall be provided for a drainage filter at weepholes as shown on the Plans.

#### Method of Measurement

#### Structure Excavation

The volume of excavation to be paid for will be the number of cubic meters measured in original position of material acceptably excavated in conformity with the Plans or as directed by the Engineer, but in no case except as noted, will any of the following volumes be included in the measurement for payment:

(1) The volume outside of vertical planes 450 mm. outside of and parallel to the neat lines of footings and the inside walls of pipe and pipe-arch culverts at their widest horizontal dimensions.





(2) The volume of excavation for culvert and sections outside the vertical plane for culverts stipulated in (1) above.

(3) The volume outside of neat lines of underdrains as shown on the Plans, and outside the limits of foundation fill as ordered by the Engineer.

(4) The volume included within the staked limits of the roadway excavation, contiguous channel changes, ditches, etc., for which payment is otherwise provided in the Specification.

(5) Volume of water or other liquid resulting from construction operations and which can be pumped or drained away.

(6) The volume of any excavation performed prior to the taking of elevations and measurements of the undisturbed ground.

(7) The volume of any material rehandled, except that where the Plans indicate or the Engineer directs the excavation after embankment has been placed and except that when installation of pipe culverts by the imperfect trench method specified in Item 500 is required, the volume of material re-excavated as directed will be included.

(8) The volume of excavation for footings ordered at a depth more than 1.5 m. below the lowest elevation for such footings shown on the original Contract Plans, unless the Bill of Quantities contains a pay item for excavation ordered below the elevations shown on the Plans for individual footings.

**Basis of Payment** 

The accepted quantities, measured as prescribed in Section 103.3, shall be paid for at the Contract unit price for each of the particular pay items listed below that is included in the Bill of Quantities. The payment shall constitute full compensation for the removal and disposal of excavated materials including labor, equipment, tools and incidentals necessary to complete the work prescribes in this Item, except as follows:

(1) Any excavation for footings ordered at a depth more than 1.5 m. below the lowest elevation shown on the original Contract Plans will be paid for as provided in Part K, Measurement and Payment, unless a pay item for excavation ordered below Plan elevation appears in the Bill of Quantities.

(2) Concrete will be measured and paid for as provided under Item 405, Structural Concrete.

(3) Any roadway or borrow excavation required in excess of the quantity excavated for structures will be measured and paid for as provided under Item 102.

(4) Shoring, cribbing, and related work required for excavation ordered more than below Plan elevation will be paid for in accordance with Part K.

Payment will be made under:

Payment Item Number	Item Description	Unit of Measurement
103(1)	Structure Excavation	Cubic Meter
103(2)	Bridge Excavation	Cubic Meter
103(3)	Foundation Fill	Cubic Meter
103(4)	Excavation ordered below Plan elevation	Cubic Meter
103(5)	Shoring, cribbing, and related work	Lump Sum
103(6)	Pipe culverts and drain excavation	Cubic Meter
Item 804(1)a	Embankment (from Structure Excavation)	

Referring to Item 104, Part C of volume II (Blue Book):

Description





This item shall consist of the construction of embankment in accordance with this Specification and in conformity with the lines, grades and dimensions shown on the Plans or established by the Engineer.

#### Material Requirements

Embankments shall be constructed of suitable materials, in consonance with the following definitions:

1.) Suitable Material – Material which is acceptable in accordance with the Contract and which can be compacted in the manner specified in this Item. It can be common material or rock.

Selected Borrow, for topping – soil of such gradation that all particles will pass a sieve with 75 mm. square openings and not more than 15 mass percent will pass the 0.075 mm. (No. 200) sieve, as determined by AASHTO T 11. The material shall have a plasticity index of not more than 6 as determined by AASHTO T 90 and a liquid limit of not more than 30 as determined by AASHTO T 89.

2.) Unsuitable Material – Material other than suitable materials such as:

(a) Materials containing detrimental quantities of organic materials, such as grass, roots and sewerage.

- (b) Organic soils such as peat and muck.
- (c) Soils with liquid limit exceeding 80 and/or plasticity index exceeding 55.
- (d) Soils with a natural water content exceeding 100%.
- (e) Soils with very low natural density, 800 kg/m3 or lower.
- (f) Soils that cannot be properly compacted as determined by the Engineer.

**Construction Requirements** 

#### General

Prior to construction of embankment, all necessary clearing and grubbing in that area shall have been performed in conformity with Item 100, Clearing and Grubbing.

Embankment construction shall consist of constructing roadway embankments, including preparation of the areas upon which they are to be placed; the construction of dikes within or adjacent to the roadway; the placing and compacting of approved material within roadway areas where unsuitable material has been removed; and the placing and compacting of embankment material in holes, pits, and other depressions within the roadway area.

Embankments and backfills shall contain no muck, peat, sod, roots or other deleterious matter. Rocks, broken concrete or other solid, bulky materials shall not be placed in embankment areas where piling is to be placed or driven.

Where shown on the Plans or directed by the Engineer, the surface of the existing ground shall be compacted to a depth of 150 mm. and to the specified requirements of this Item.

Where provided on the Plans and Bill of Quantities the top portions of the roadbed in both cuts and embankments, as indicated, shall consist of selected borrow for topping from excavations.

#### Methods of Construction

Where there is evidence of discrepancies on the actual elevations and that shown on the Plans, a preconstruction survey referred to the datum plane used in the approved Plan shall be undertaken by the Contractor under the control of the Engineer to serve as basis for the computation of the actual volume of the embankment materials.





When embankment is to be placed and compacted on hillsides, or when new embankment is to be compacted against existing embankments, or when embankment is built one-half width at a time, the existing slopes that are steeper than 3:1 when measured at right angles to the roadway shall be continuously benched over those areas as the work is brought up in layers. Benching will be subject to the Engineer's approval and shall be of sufficient width to permit operation of placement and compaction equipment. Each horizontal cut shall begin at the intersection of the original ground and the vertical sides of the previous cuts. Material thus excavated shall be placed and compacted along with the embankment material in accordance with the procedure described in this Section.

Unless shown otherwise on the Plans or special Provisions, where an embankment of less than 1.2 m. below subgrade is to be made, all sod and vegetable matter shall be removed from the surface upon which the embankment is to be placed, and the cleared surfaced shall be completely broken up by plowing, scarifying, or steeping to a minimum depth of 150 mm. except as provided in Subsection 102.2.2. Sod not required to be removed shall be thoroughly disc harrowed or scarified before construction of embankment. Wherever a compacted road surface containing granular materials lies within 900 mm. of the subgrade, such old road surface shall be scarified to a depth of at least 150 mm. whenever directed by the Engineer. This scarified material shall be compacted as provided in Subsection 104.3.3.

When shoulder excavation is specified, the roadway shoulders shall be excavated to the depth and width shown on the Plans. The shoulder material shall be removed without disturbing the adjacent existing base course material, and all excess excavated materials shall be disposed off as provided in Subsection 102.2.3. If necessary, the areas shall be compacted before being backfilled.

Roadway embankment of earth material shall be placed in horizontal layers not exceeding 200 mm., loose measurement, and shall be compacted as specified before the next layer is placed. However, thicker layer maybe placed if vibratory roller with high compactive effort is used provided that density requirement is attained and as approved by the Engineer. Trial section to this effect must be conducted and approved by the Engineer. Effective spreading equipment shall be used on each lift to obtain uniform thickness as determined in the trial section prior to compaction. As the compaction of each layer progresses, continuous leveling and manipulating will be required to assure uniform density. Water shall be added or removed, if necessary, in order to obtain the required density. Removal of water shall be accomplished through aeration by plowing, blading, discing, ot other methods satisfactory to the Engineer.

Where embankment is to be constructed across low swampy ground that will not support the mass of trucks or other hauling equipment, the lower part of the fill may be constructed by dumping successive loads in a uniformly distributed layer of a thickness not greater than necessary to support the hauling while placing subsequent layers.

When excavated material contains more than 25 mass percent of rock larger 150 mm. in greatest diameter and cannot be placed in layers of the thickness prescribed without crushing pulverizing or further breaking down the pieces resulting from excavation methods, such materials may be placed on the embankment in layers not exceeding in thickness the approximate average size of the larger rocks, but not greater than 600 mm.

Even though the thickness of layers is limited as provided above, the placing of individual rocks and boulders greater than 600 mm. in diameter will be permitted provided that when placed, they do not exceed 1200 mm. in height and provided they are carefully distributed, with the interstices filled with finer material to form a dense and compact mass.

Each layer shall be leveled and smoothed with suitable leveling equipment and by distribution of spalls and finer fragments of earth. Lifts of material containing more than 25 mass percent of rock larger than 150 mm. in greatest dimensions shall not be constructed above an elevation 300 mm. below the finished subgrade. The balance of the embankment shall be composed of suitable material smoothed and placed in layers not exceeding 200 mm. in loose thickness and compacted as specified for embankments.

Dumping and rolling areas shall be kept separate, and no lift shall be covered by another until compaction complies with the requirements of Subsection 104.3.3.

Hauling and leveling equipment shall be so routed and distributed over each layer of the fill in such a manner as to make use of compaction effort afforded thereby and to minimize rutting and uneven compaction.





#### 104.3.3. Compaction

**Compaction Trials** 

Before commencing the formation of embankments, the Contractor shall submit in writing to the Engineer for approval his proposals for the compaction of each type of fill material to be used in the works. The proposals shall include the relationship between the types of compaction equipment, the number of passes required and the method of adjusting moisture content. The Contractor shall carry out full scale compaction trials on areas not less than 10 m. wide and 50 m. long as required by the Engineer and using his proposed procedures or such amendments thereto as may be found necessary to satisfy the Engineer that all the specified requirements regarding compaction can be consistently achieved. Compaction trials with the main typed of fill material to be used in the works shall be completed before work with the corresponding materials will be allowed to commence.

Throughout the periods when compaction of earthwork is in progress, the Contractor shall adhere to the compaction procedures found from compaction trials for each type of compaction equipment employed and each degree of compaction specified.

#### Earth

The Contractor shall compact the material placed in all embankment layers and the material scarified to the designated depth below subgrade in cut sections, until a uniform density of not less than 95 mass percent of the maximum dry density determined by AASHTO T 99 Method C, is attained, at a moisture content determined by the Engineer to be suitable for such density. Acceptance of compaction may be based on adherence to as approved roller pattern developed as set forth in Item 106, Compaction Equipment and Density Control Strips.

The Engineer shall during progress of the Work, make density tests of compacted material in accordance with AASHTO T 191, T 205, or other approved field density tests, including the use of properly calibrated nuclear testing devices. A correction for coarse particles may be made in accordance with AASHTO T 224. If, by such tests, the Engineer determines that the specified density and moisture conditions have not been attained, the Contractor shall perform additional work as may be necessary to attain the specified conditions.

At least one group of three in-situ density tests shall be carried out for each 500 m2 of each layer of compacted fill.

#### Rock

Density requirements will not apply to portions of embankments constructed of materials which cannot be tested in accordance with approved methods.

Embankment materials classified as rock shall be deposited, spread and leveled the full width of the fill with sufficient earth or other fine material so deposited to fill the interstices to produce a dense compact embankment. In addition, one of the rollers, vibrators, or compactors meeting the requirements set forth in Subsection 106.2.1 Compaction Equipment, shall compact the embankment full width with a minimum of three-complete passes for each layer of embankment.

#### 104.3.5. Protection of Structure

If embankment can be deposited on one-side only of abutments, wing walls, piers or culvert headwalls, care shall be taken that the area immediately adjacent to the structure is not compacted to the extent that I will cause overturning of, or excessive pressure against the structure. When noted on the Plans, the fill adjacent to the end bent of a bridge shall not be placed higher than the bottom of the backfill of the bent until the superstructure is in place. When embankment is to be placed on both sides of a concrete wall or





box type structure, operations shall be so conducted that the embankment is always at approximately the same elevation on both sides of the structure.

#### 104.3.6. Rounding and Warping Slopes

Rounding-Except in solid rock, the tops and bottoms of all slopes, including the slopes of drainage ditches, shall be rounded as indicated on the Plans. A layer of earth overlaying rock shall be rounded above the rock as done in earth slopes.

Warping-adjustments in slope shall be made to avoid injury in standing trees or marring of weathered rock, or to harmonize with existing landscape features, and the transition to such adjusted slopes shall be gradual. At intersections of cuts and fills, slopes shall be adjusted and warped to flow into each other or into the natural ground surfaces without noticeable break.

#### 104.3.7. Finishing Roadbed and Slopes

After the roadbed has been substantially completed, the full width shall be conditioned by removing any soft or other unstable material that will not compact properly or serve the intended purpose. The resulting areas and all other low sections, holes or depressions shall be brought to grade with suitable selected material. Scarifying, blading, dragging, rolling, or other methods of work shall be performed or used as necessary to provide a thoroughly compacted roadbed shaped to the grades and cross-sections shown on the Plans or as staked by the Engineer.

All earth slopes shall be left with roughened surfaces but shall be reasonably uniform, without any noticeable break, and in reasonably close conformity with the Plans or other surfaces indicated on the Plans or as staked by the Engineer, with no variations therefrom readily discernible as viewed from the road.

#### 104.4 Method of Measurement

The quantity of embankment to be paid for shall be the volume of material compacted in place, accepted by the Engineer will be paid under Embankment and such payment will be deemed to include the cost of excavating, hauling, stockpiling and all other costs incidental to the work.

#### 104.5 Basis of Payment

The accepted quantities, measured as prescribed in Section 104.4, shall be paid for at the Contract unit price for each of the Pay Items listed below that is included in the Bill of Quantities. The payment shall continue full compensation for placing and compacting all materials including laor, equipment, tools and incidentals necessary to complete the work prescribed in this Item.

Payment will be made under:

Payment Item	Item	Unit of
Number	Description	Measurement
104(1)	Embankment	Cubic Meter
104(2)	Selected Borrow for topping, Case 1	Cubic Meter
104(3)	Selected Borrow for topping, Case 2	Cubic Meter
104(4)	Earth Berm	Cubic Meter





# Item 804(1)b – Embankment (from Borrow)

Referring to Item 104, Part C of volume II (Blue Book):

# Item 804(4) – Gravel Fill

Referring to Item 104, Part C of volume II (Blue Book):

# **Item 900 – Reinforced Concrete**

#### 900.1 Description

This Item shall consist of furnishing, placing, and finishing concrete in buildings and related structures, flood control and drainage, ports, and water supply structures in accordance with this specification and conforming to the lines, grades, and dimension shown on the plans.

#### 900.2 Material Requirements

#### 900.2.1 Portland Cement

This shall conform to the requirement of Item 700, Volume II (Blue Book), Hydraulic Cement.

#### 900.2.2 Concrete Aggregates

Concrete aggregate shall conform to the requirements of subsection 311.2.2 and 311.2.3 under Item 311 of Volume II (Blue Book) and ASTM C 33 for lightweight aggregates, except that aggregates failing to meet these specifications but which have been shown by special that or actual service to produce concrete of adequate strength and durability may be used under method (2) of determining the proportion of concrete, where authorized by the Engineer.

Except as permitted elsewhere in this section, the maximum size of the aggregate shall be not larger than one-fifth (1/5) of the narrowest dimensions between sides of forms of the member for which the concrete is to be used nor larger than three-fourths of the minimum clear spacing between individual reinforcing bars or bundle of bars or pretensioning strands.

#### 900.2.2.1 Aggregate Tests

Samples of the fine and coarse aggregates to be used shall be selected by the Engineer for tests at least 30 days before the actual concreting operations are to begin. It shall be the responsibility of the Contractor to designate the source or sources of aggregate to give the Engineer sufficient time to obtain the necessary samples and submit them for testing.

No aggregate shall be used until official advise has been received that it has satisfactorily passed all tests at which time written authority shall be given for its use.

#### 900.2.3 Water

Water used in mixing concrete shall conform to the requirement of subsection 311.2.4 under Item 311, Part E of Volume II (Blue Book).

#### 900.2.4 Metal Reinforcement

Reinforcing steel bars shall conform to the requirements of the following specifications:





Deformed & Plain Billet Steel	(ASTM A 615)
Bars for Concrete Reinforcement	AASHTO M 31
Deformed Rail – Steel and Plain Bars	
for Concrete Reinforcement	ASTM A 616
Deformed A x b – Steel and Plain Bars	
for Concrete Reinforcement	ASTM A 617

If reinforcing bars are to be welded, these ASTM specifications shall be supplemented by requirements assuring satisfactory weldability:

Bar and Rod Mats for Concrete Reinforcement	<b>ASTM A 187</b>
Cold-Drawn Steel Wire for Concrete Reinforcement	(ASTM A 82)
	AASHTO M 32
Welded Steel Wire Fabric for Concrete Reinforcement	(ASTM A 185)
	AASHTO M55

Except that the weld shear strength requirement of those specification shall be extended to include a wire size differential up to and including six gages:

Wire and Strands for Prestressed Concrete	<b>ASTM A 416</b>
	<b>ASTM A 421</b>

Used in making strands for post-tensioning shall be cold-drawn and either stress-relieved in the case of uncoated strands, or hot-dip galvanized in thecase of galvanized strands.

High strength alloy steel bar for post-tensioning shall be proofstressed to 90% of the granted tensile strength. After proofstressing, the bars shall conform to the following minimum properties:

1000 MPa
0.90 fs'
4 percent
25 percent
ASTM A 36
ASTM A 53
<b>ASTM A 377</b>

#### 900.2.5 Admixures

Air-entraining admixtures, if used, shall conform to ASTM C 260.

Water-reducing admixtures, retarding admixtures, water-reducing and retarding admixtures and water reducing and accelerating admixtures, if used, shall conform to the requirements of ASTM C 494.

#### 900.2.6 Storage of Materials

Cement and aggregates shall be stored in such a manner as to prevent their deterioration or the intrusion of foreign matter. Cement shall be stored immediately upon arrival on the site of the work, in substantial, waterproof bodegas, with a floor raised from the ground sufficiently high to be free from dampness. Aggregates shall be stored in such a manner as to avoid the inclusion of foreign materials.

#### 900.3 Construction Requirements

Notations: The notations used in these regulations are defined as follows:

Fc' = compressive strength of concrete

Fsp = ratio of splitting tensile strength to square foot of compressive strength.

#### 900.3.1 Concrete Quality

All plans submitted for approval or used for any project shall clearly show the specified strength, fc', of concrete of the specified age for which each part of the structure was designed.





Concrete that will be exposed to sulfate containing or other chemically aggressive solutions shall be proportioned in accordance with: Recommended Practice for Selecting Proportions for Concrete (ACI 613)" and Recommended Practice for Selecting Proportions for Structural Lightweight Concrete (ACI 613A)."

#### 900.3.2 Methods of Determining the Proportions of Concrete

The determination of the proportions of cement, aggregate, and water to attain the required strengths shall be made by one of the following methods, but lower water-cement ratios may be required for conformance with the quality of concrete.

Method 1. Without Preliminary Test

Where preliminary test data on the materials to be used in the concrete have not been obtained the watercement ratio for a giver strength of concrete shall not exceed the values shown in Table 900.1. When strengths in excess of 281 kilograms per square centimeter (4000 pounds per square inch) are required or when light weight aggregates or admixtures (other than those exclusively for the purpose of entraining air) are used, the required water-cement ratio shall be determined in accordance with Method 2.

Method 2. For combination of materials previously evaluated or to be established by trial mixtures.

Water-cement ratios for strengths greater than that shown in Table 900.1 may be used provided that the relationship between strength and water-cement ratio for the materials to be used has been previously established by reliable test data and the resulting concrete satisfies the requirements of concrete quality.

Where previous data are not available. Concrete trial mixtures having proportions and consistency suitable for the work shall be made using at least three different water-cement ratios (or cement content in the case of lightweight aggregates) which will produce a range of strengths encompassing those required for the work. For each water-cement ratio (or cement content) at least three specimens for each age to be tested shall be made, cured and tested for strength in accordance with ASTM C 39 and C 192.

The strength test shall be made at 7, 14, 28 days at which the concrete is to receive load, as indicated on the plans. A curve shall be established showing the relationship between water-cement ratio (or cement content) and compressive strength. The maximum permissible water-cement ratio for the concrete to be used in the structure shall be that shown by the curve to produce an average strength to satisfy the requirements of the strength test of concrete provided that the water-cement ratio shall be no greater than that required by concrete quality when concrete that is to be subjected to the freezing temperatures which weight shall have a water-cement ratio not exceeding 6 gal. per bag and it shall contain entrained air.

Where different materials are to be used for different portions of the work, each combination shall be evaluated separately.

#### 900.3.3 Concrete Proportions and Consistency

The proportions of aggregate to cement for any concrete shall be such as to produce a mixture which will work readily into the corners and angles of the form and around reinforcement with the method of placing employed on the work, but without permitting the materials to segregate or excess free water to collect on the surface. The methods of measuring concrete materials shall be such that the proportions can be accurately controlled and easily checked at any time during the work.

900.3.4 Sampling and Testing of Structural Concrete

As work progress, at least one (1) set of sample consisting of three (3) concrete cylinder test specimens,  $150 \times 300$  mm. shall be taken from each class of concrete placed each day, and each set to represent not more than 75 cu. m. of concrete.





#### 900.3.5 Consistency

Concrete shall have a consistency such that it will be workable in the required position. It shall be such a consistency that it will flow around reinforcing steel but individual particles of the coarse aggregate when isolated shall show a coating or mortar containing its proportionate amount of sand. The consistency of concrete shall be gauged by the ability of the equipment to properly placed it and not by the difficulty of mixing water shall be determined by the Engineer and shall not be varied without his consent. Concrete as dry as it is practical to place with the equipment specified shall be used.

#### 900.3.6 Strength Test of Concrete

When strength is a basis for acceptance, each class of concrete shall be represented by at least five test (10 specimens). Two specimens shall be made for each test at a given age, and not less than one test shall be made for each 150 cu. yd. of structural concrete, but there shall be at least one test for each days concreting. The Building Official may require a reasonable number of additional tests during the progress of the work. Samples from which compression test specimens are molded shall be secured in accordance with ASTM C 172. Specimens made to check the adequacy of the proportions for strength of concrete or as a basis for acceptance of concrete shall be made and laboratory-cured in accordance with ASTM C 31. Additional test specimens cured entirely under field conditions may be required by the Building Official to check the adequacy of the concrete. Strength tests shall be made in accordance with ASTM C 39.

The age for strength tests shall be 28 days or, where specified, the earlier age at which the concrete is to receive its full load or maximum stress. Additional test may be made at earlier ages to obtain advance information on the adequacy of strength development where age-strength relationships have been established for the materials and proportions used.

To conform to the requirements of this item:

1. For structures designed in accordance with the working stress design method of this chapter, the average of any five consecutive strength tests of the laboratory-cured specimens representing each class of concrete shall be equal on or greater than the specified strength, fc', and not more than 20 percent of the strength test shall have values less than that specified.

2. For structures designed in accordance with the ultimate strength design method of this chapter, and for prestressed structures the average of any three consecutive strength test of the laboratory cured specimens representing each class of concrete shall be to or greater than the specified strength. Fc' and not more than 10 percent of the strength tests shall have values less than the specified strength.

When it appears that the laboratory-cured specimens will fail to conform to the requirements for strength, the Engineer shall have the right to order changes in the concrete sufficient to increase the strength to meet these requirements. The strengths of the specimens cured on the job are intended to indicate the adequacy of protection and curing of the concrete and may be used to determine when the forms may be stripped, shoring removed, or the structure placed in service. When, in the opinion of the Building Official, the strengths of the job-cured specimens, the contractor may be required to improve the procedures for protection and curing the concrete, or when test of field-cured cylinders indicate deficiencies in protection and curing, the Engineer may require test in accordance with ASTM Specification C 42 or order load tests as outlined in the load tests of structures for that portion of the structure where the questionable concrete has been placed.

# 900.3.7 Splitting Tensile Test of Concrete

To determine the splitting ratio, Fsp, for a particular aggregate, test of concrete shall be made as follows:

1. Twenty four (24) 15 cm. dia. by 30 cm long (6 in. dia. by 12 in. long) cylinders shall be made in accordance with ASTM C 192, twelve at a compressive strength level of approximately 219 kilograms per square centimeter (3000 psi) and twelve at approximately 280 kilograms per square centimeter (4000 psi) or 350 kilograms per square centimeter (5000 psi). After 7 days moist curing followed by 21 days drying at 23C (73F) and 50 percent relative humidity, eight of the test cylinders at each of the two strength levels shall be tested for splitting strength and four for compressive strength.





2. The splitting tensile strength shall be determine in accordance with ASTM C 496, and compressive strength in accordance with ASTM C 39.

The ratio, Fsp, of splitting tensile strength to the square root of compressive strength shall be obtained by using the average of all 16 splitting tensile test and all 8 compressive tests.

Minimum Strength, Concrete other than fill, shall have a minimum compressive strength at 28 days of 140 kilograms per square centimeter (2000 psi).

#### 900.3.8 Batching

Batching shall conform to the requirements of Item 405, Structural Concrete.

#### 900.3.9 Mixing and Delivery

Mixing and delivery shall conform to the requirements of Item 405, Structural Concrete.

#### 900.4 Concrete Surface Finishing: General

This shall be in accordance with Item 407, Concrete Structures.

#### 900.5 Curing Concrete (See subsection 407)

#### 900.6 Acceptance of Concrete

The strength of concrete shall be deemed acceptable if the average of 3 consecutive strength test results is equal to or exceed the specified strength and no individual test result falls below the specified strength by more than 15 %.

Concrete deemed to be not acceptable using the above criteria may be rejected unless contractor can provide evidence, by means of core tests, that the quality of concrete represented by the failed test result is acceptable in place. Three (3) cores shall be obtained from the affected area and cured and tested in accordance with AASHTO T24. Concrete in the area represented by the cores will be deemed acceptable if the average of cores is equal to or at least 85% and no sample core is less than 75% of the specified strength otherwise it shall be rejected.

#### 900.7 Method of Measurement

The quantity of concrete to be paid shall be the quantity shown on the Bid Schedule, unless changes in design are made in which cases the quantity shown in the Bid Schedule will be adjusted by the amount of the change for the purpose of payment. No deduction will be made for the volume occupied by the pipe less than 101 mm. (4") in diameter nor for reinforcing steel, anchors, weepholes or expansion materials.

#### 900.8 Basis of Payment

The accepted quantities of structural concrete completed in place will be paid for at the contract unit price for cubic meter as indicated on the Bid Schedule.

Pay Item and Description	Unit of Measurement	
Structural Concrete	Cubic Meter	

Such prices and payment shall be full compensation for furnishing all materials, including metal water stops, joints, joint fillers, weep holes, and rock backing and timber bumpers; for all form and false work; for mixing, placing, furnishing, and curing the concrete; and for all labor, materials, equipment, tools, and incidentals necessary to complete the item, except that reinforcing steel shall be paid for at the contract unit price per kilogram for reinforcing steel metal pipes and drains, metal conduits and ducts, and metal expansion angles shall be paid for as structural steel that when the proposal does not include an item for structural steel these miscellaneous metal parts shall be paid for as reinforcing steel.





# 902 Reinforcing Steel

#### Description

This item shall consist of furnishing, bending, fabricating and placing of steel reinforcement of the type, size, shape and grade required in accordance with this Specification and in conformity with the requirements shown on the Plans or as directed by the Engineer.

#### **Material Requirements**

Reinforcing steel shall meet the requirements of Item 710, Reinforcing Steel and Wire Rope.

#### **Construction Requirements**

#### Protection of Reinforcing Steel

Steel reinforcement shall be stored above the surface of the ground upon platforms, skid or other supports and shall be protected as far as practicable from mechanical injury and surface deterioration caused by exposure to conditions producing rust. When placed in the worked, reinforcement shall be free from dirt, detrimental rust, loose scale, paint, grease, oil, or other foreign materials. Reinforcement shall be free from injurious defects such as cracks and laminations. Rust, surface seams, surface irregularities or mill scale will not be cause for rejection, provided the minimum dimension, cross sectional area and tensile properties of the material meets the physical requirements for the size and grade of steel specified.

#### Bending

All reinforcing bars requiring bending shall be cold-bent to the shapes shown on the Plans or required by the Engineer. Bars shall be bent around a circular pin having the following diameter (D) in relation to the diameter of the bar (d):

Bends and Hooks	
Nominal diameter, (d), mm	Pin diameter (D)
10 to 20	6d
25 to 28	8d
32 and greater	10d

#### Placing and Fastening

All steel reinforcement shall be accurately placed in the position shown on the Plans and firmly held there during the placing and setting of the concrete. Bars shall be tied at all intersections except where spacing is less than 300 mm in each direction, in which case, alternate intersections shall be tied. Ties shall be fastened on the inside. Distance from the forms shall be maintained by means of stays, blocks, ties, hangers, or other approved supports, so that it does not vary from the position indicated on the Plans by more than 6 mm. Blocks for holding reinforcement from contact with the forms shall be precast mortar blocks or by other equally suitable devices. The use of pebbles, pieces of broken stone or brick, metal pipe and wooden blocks shall not be permitted. The minimum distance between bars shall be 40 mm.





Reinforcement any member shall be placed, inspected and approved by the Engineer before the concrete begins. Concrete placed in violation of this provision may be rejected and removal may be required.

#### Splicing

All reinforcement shall be furnished in the full lengths indicated on the Plans. Splicing of bars except where shown on the Plans will not be permitted without the written approval of the Engineer. Splices shall be staggered as far as possible and with a minimum separation of not less than 40 bar diameters. Not more than one-third of the bars may be spliced in the same cross-section, except where shown on the Plans.

Unless otherwise shown on the Plans, bars shall be tapped a minimum distance of:

Splice	Grade 40	Grade 60	But not less than
Tension	24 bar dia.	36 bar dia	300 mm
Compression	20 bar dia	24 bar dia	300 mm

In tapped splices, the bars shall be placed in contact and wired together. Lapped splices will not be permitted at locations where the concrete section is insufficient to provide minimum clear distance of one and one-third (1 1/3) the maximum size of coarse aggregate between the splice and the nearest adjacent bar. Welding of reinforcing steel shall be done only if detailed on the Plans or if authorized by the Engineer in writing. Spiral reinforcement shall be spliced by lapping at least one and a half turns or by butt welding unless otherwise shown on the Plans.





# 903 Forms and Falsework

#### **Formwork Construction**

Concrete forms shall be mortar-tight, true to the dimensions, lines and grades of the structure and with sufficient strength, rigidity, shape and surface smoothness as to leave the finished works true to the dimension shown on the Plans or required by the Engineer and the surface finish as specified.

The inside surfaces of form shall be cleaned of all dirt, mortar and foreign material. Forms which will later be removed shall be thoroughly coated with form oil prior to use. The form oil shall be of commercial quality form oil or other approved coating which will permit the ready release of the forms and will not discolor the concrete.

Concrete shall not be deposited in the forms until all work in connection with constructing the forms has been completed, all inspected and approved said forms and materials. Such work shall include the removal of all dirt, chips, sawdust and other foreign material from the forms.

The rate of depositing concrete in forms shall be such to prevent bulging of the forms or form panels in excess of the deflections permitted by this Specification. Forms shall have sufficient strength to withstand the pressure resulting from placement and vibration of the concrete, and shall be maintained rigidly in correct position

#### **Removal of Forms and Falsework**

Forms and falsework shall not be removed without the consent of the Engineer. The Engineer's consent shall not relieve the Contractor of responsibility for the safety of the work. Blocks and bracing shall be removed at the time the forms are removed and in no case shall any portion of the wood forms be left in the concrete.

Falsework removal for continuous or cantilevered structures shall be as directed by the Engineer or shall be such that the structure is gradually subjected to its working stress.

When concrete strength tests are used for removal of forms and supports, such removal should not begin until the concrete has attained the percentage of the specified design strength shown in the table below;

# Table 414.1 – Requirements for Removal of Forms

Element	Minimum Time	Minimum Percentage Design Strength
Centering under beams frames or arches, girders	14 days	80 %
Floor slabs:	14 days	70 %
Walls	1 day	70 %
Columns	2 days	70 %
Sides of Beams and all other vertical surfaces	1 day	70 %

Forms and falsework shall not be released from under concrete without first determining if the concrete has gained adequate strength without regard to the time element. In the absence of strength determination, the forms and falsework are to remain in place until removal is permitted by the Engineer.





To facilitate finishing, forms used on ornamental work, railing, parapets and exposed vertical surfaces shall be removed in not less than 12 or more than 48 hours, depending upon the weather condition of concrete in columns, forms shall always be removed from them before the removal of shoring from beneath beams and girders. The Unit of Measurement is Cubic meter.

# **1046 Masonry Works**

#### Description

The work includes all labor, materials, tools and equipment necessary to install concrete masonry and all appurtenant work in connection with the work as shown on the Drawings and Specifications.

#### **Materials Requirements**

Concrete masonry unit work of the type indicated shall be provided and shall be properly coordinated with the work of their trades. The source of supply of materials, which will affect the appearance of the finished work, shall be changed after the work has started.

#### **Concrete Hollow Blocks**

Concrete hollow blocks shall be standard machine fabricated and shall have fine and even texture and well-defined edges. CHB shall conform to the requirements of ASTM Specifications C 90, grade with minimum compressive strength of 2.45 MPa (350 psi) (average of 5 specimens). Samples shall be tested and submitted to the Engineer. Dimensions and tolerances shall be as individually specified on the Plans.

#### **Mortar and Grout**

Unless otherwise indicated on the Plans, masonry mortar shall be composed of one (1) part Portland cement, and two (2) parts fine aggregate by volume to which hydrated lime has been added in an amount equal to ten (10) mass percent of the cement. For masonry walls not exceeding 1,8 m (1.6) in height, a mortar composed of one (1) part masonry cement and two (2) parts fine aggregate by volume maybe substituted for the above mixture of Portland cement, lime and fine aggregate. Grout shall be of the same materials and proportion as mortar to which additional water shall be added to produce a consistency for pouring without segregation. Masonry cement shall conform to the requirements of AASHTO M 150 – 74 (ASTM C 91). Fine aggregate shall conform to the requirements of AASHTO M 45 (ASTM C 144). Water shall conform to the requirements of Item 714, Water.

#### **CHB Wall Reinforcement**

1. Vertical and Horizontal Reinforcement

Unless otherwise specified, the vertical and horizontal reinforcements for CHB shall be 10mm diameter at 400 for all wall thick nesses. Lap splices shall be 300 mm long (minimum).

2. Dowels

Where CHB walls adjoin R.C. columns and beams provide dowels on R.C. column and beams prior to pouring to match CHB wall reinforcement size and spacing. Dowels shall be 600 mm long unless noted otherwise.

- 3. Movement Gaps
  - Where the top of CHB wall adjoins a beam provide 50 mm gap to be filled with a soft material like styrophor.
  - Where the sides of a CHB wall adjoin a column provide 50 mm gap to be filled with soft material like styropor. Rebars shall be retained for stability.





#### 4. Anchors

Where columns and beams poured without the CHB wall dowels, provide 16 mm diameter expansion bolts to match CHB reinforcement spacing. These anchors shall be drilled and hammered in placed. No chipping off of concrete columns and beams is allowed unless otherwise permitted by the Engineer.

#### **Construction Requirements**

#### Workmanship

Units shall be set plumb and true to line with level horizontal joints. Hollow units shall be laid with full mortar coverage on horizontal and vertical face shells, and at least 50 percent of the cells shall be filled with grout, the cells containing vertical reinforcements to be among those to be filled up. All cells of CHB walls from footing up to at least the ground floor level shall be filled up. Solid units shall be laid with full head and bed joints. Joints shall be uniform and approximately 10 mm wide unless otherwise indicated.

Unless otherwise shown on the drawings, joints of exterior concrete masonry units that will be exposed and painted shall be cut flush and tooled finished with a 6.5 mm dept "V" joint for horizontal joints. Vertical joints between the horizontal joints shall be tooled flush. Joints of interior concrete masonry units shall be cut flush, and the blocks shall be given a cement plaster finish except as otherwise shown on the Drawings. The minimum of cement plaster shall be 10 mm.

#### **Placing Reinforcing Bars and Grouting**

All reinforcing steel, except dowels in concrete, shall be accurately set in strict accordance with the Drawings and the notes thereon. Vertical steel shall be secured firmly in place by means of frames or other suitable devices. Horizontal steel may be placed as the work progresses. In any core containing reinforcement, the distance between any masonry and the reinforcement shall be at least 12.7 mm (1/2 in) at all points. The masonry contractor shall furnish all tiles, spacers and supports required to hold steel in position during grouting. Cores shall be grouted in lifts not exceeding 1.22 m (4 ft) in height. Grout shall be thoroughly rodded. Splices in reinforcing bars shall be lapped at a distance sufficient to develop the stress in the bar, but not less that 40 bar diameters.

Concrete hollow blocks shall be laid with all cells completely grouted from the wall footing up to the ground level. The rest of the concrete hollow blocks above ground shall have at least 50 percent of the cells grouted, including those containing the vertical reinforcements.

#### **Method of Measurement**

All masonry works shall be measured in square meters installed complete with plastering, mortar and grout and installing reinforcing bars as shown on the drawing and prescribed in the specification.

#### **Basis for Payments**

The accepted quantities measured as prescribed in Sub-Section 901.4 shall be paid for at the appropriate contract unit price for the pay item listed below as shown in the Bill of Quantities, which

price and payment shall be full compensation for furnishing all materials, including all form and false work; for mixing, placing, furnishing, and curing the concrete; and for all labor, materials, equipment, tools and incidentals to complete the item.

Payment shall be made under:

Pay Item No.

Description

Unit of Measurement





square meter  $(m^2)$ 

414 (2) 100 mm thick CHB Walls With Cement plaster finish

# **1027 Cement Plaster Finish**

### 1027.1 Description

This Item shall consist of furnishing all cement plaster materials, labor, tools and equipment required in undertaking cement plaster finish as shown on the Plans and in accordance with this Specification.

#### **1027.2** Material Requirements

Manufactured materials shall be delivered in the manufacturer's original unbroken packages or containers which are labeled plainly with the manufacturer's name and trademark.

1027.2.1 Cement

Portland cement shall conform with the requirements as defined in Item 700 - Hydraulic Cement.

1027.2.2 Hydrated Lime

Hydrated lime shall conform with the requirements as defined in Item 701 - Hydrated Lime.

## 1027.2.3 Fine Aggregates

Fine aggregates shall be clean, washed sharp river sand and free from dirt, clay, organic matter or other deleterious substances. Sand derived from crushed gravel or stone may be used with the Engineer's approval but in no case shall such sand be derived from stone unsuitable for use as coarse aggregates.

# **1027.3** Construction Requirements

#### 1027.3.1 Mixture

- a) Mortar mixture for brown coat shall be freshly prepared and uniformly mixed in the proportion by volume of one (1) part Portland Cement, three (3) parts sand and one fourth (1/4) part hydrated lime.
- b) Finish coat shall be pure Portland cement properly graded conforming to the requirements of Item 700, Hydraulic Cement and mixed with water to approved consistency and plasticity.





- a) After removal of formworks reinforced concrete surfaces shall be roughened to improve adhesion of cement plaster.
- b) Surfaces to receive cement plaster shall be cleaned of all projections, dust, loose particles, grease and bond breakers. Before any application of brown coat is commenced all surfaces that are to be plastered shall be wetted thoroughly with clean water to produce a uniformly moist condition.

#### 1027.3.3 Application

- a) Brown coat mortar mix shall be applied with sufficient pressure starting from the lower portion of the surface to fill the grooved and to prevent air pockets in the reinforced concrete/ masonry work and avoid mortar mix drooping. The brown coat shall be lightly broomed/ or scratch before surface had properly set and allowed to cure.
- b) Finish coat shall not be applied until after the brown coat has seasoned for seven days and corrective measures had been done by the Contractor on surfaces that are defective. Just before the application of the finish coat, the brown coat surface shall be evenly moistened with potable water. Finish coat shall be floated first to a true and even surface, then trowel in a manner that will force the mixture to penetrate into the brown coat. Surfaces applied with finish coat shall then be smooth with paper in a circular motion to remove trowel marks, checks and blemishes. All cement plaster finish shall be 10 mm. thick minimum, on vertical concrete and/ or masonry walls.

Whenever indicated on the Plans to be "simulated red brick finish", the Contractor shall render brick design on plaster surface before brown coat had properly set and then allowed to dry. Cement plaster shall not be applied directly to:

- a) Concrete or masonry surface that had been coated with bituminous compound and,
- b) Surfaces that had been painted or previously plastered.

#### 1027.3.4 Workmanship

Cement plaster finish shall be true to details and plumbed. Finish surface shall have no visible junction marks where one (1) day's work adjoins the other. Where directed by the Engineer or shown on the Plans vertical and horizontal groove joints shall be 25 mm wide and 10 mm deep.

#### 1027.4 Method of Measurement

All cement plaster finish shall not be measured in square meters or part thereof for work actually completed in the building.





# 1027.5 Basis of Payment

The work quantified and determined as provided in the Bill of Quantities shall be paid for at the Contract Unit price which price constitutes full compensation including labor, materials, tools and equipment and incidentals necessary to complete this Item.

Payment will be made under:

Pay Item No.	Description	Unit of Measure	ement
1027 (a)	Cement plaster finish	Square Meter (n	1 <sup>2</sup> )
1027 (b)	Simulated red brick (Wa	ll)	Square Meter (m <sup>2</sup> )





# 1100 Conduit, Boxes, and Fittings

ITEM 1100 - CONDUITS, BOXES & FITTINGS

#### 1100.1 Description

This Item shall consist of the furnishing and installation of the complete conduit work consisting of electrical conduits; conduit boxes such as junction boxes, pull boxes, utility boxes, octagonal and square boxes; conduit fittings such as couplings, locknuts and bushings and ohter electrical materials needed to complete the conduit roughing-in work of this project.

#### 1100.2 Material Requirements

All materials shall be brand new and shall be of the approved type meeting all the requirements of the Philippine Electrical Code and bearing the Philippine Standard Agency (PSA) mark.

#### Conduits

Conduits shall be standard rigid steel, zinc coated or galvanized. Intermediate metal conduit may be used if shown or specified on the approved Plans. PVC conduits if required shall be Schedule 40. Enamel coated steel conduits and conduits with rough inner surfaces are not acceptable.

#### Conduit Boxes

All conduit boxes shall be Code gauge steel and galvanized. Outlet boxes shall be galvanized pressed steel of standard make. In general, outlet boxes shall be at least 100 mm square or octagonal, 53 mm deep and 16 mm minimum gauge.

#### **Conduit Fittings**

All conduit fittings such as locknuts and bushings shall be galvanized of standard make.

#### 1100.3 Construction Requirements

All works throughout shall be executed in the best practice in a workmanlike manner by qualified and experienced electricians under the immediate supervision of a duly licensed Electrical Engineer.

#### Conduits

Conduits should be cut square with a hacksaw and reamed. Bends shall be made with the required radius. In making bends only conduit bending apparatus will be used. The use of a pipe tee or vise for bending conduits shall not be permitted. Conduits which have been crushed, deformed or flattened shall not be installed. No running thread shall be allowed. Conduit runs crossing construction joints of the building shall be provided with standard expansion fittings of the approved type.





No conduits shall be used in any system smaller than 12 mm diameter electric trade size nor shall, have more than four (4) 90-degree bends in any one run and where necessary, pull boxes shall be provided.

All ends of conduits which are left empty in cabinets and conduit boxes shall be plugged with lead or approved pipe caps so as to prevent the entranceof white ants and dirt within the conduit system. Pull wires shall be inserted in the empty ducts before they are closed with lead or pipe caps and shall be left therein for tuture use.

On exposed work, all pipes and outlet boxes shall be secured by means of galvanized metal clamps which shall be held in place by means of machine screws. When running over concrete surfaces, the screws shall be held in place by means of expansion sleeves for big pipes and rolled lead sheet for small pipes. All pipes shall be run at right angles to and parallel with the surrounding walls. No diagonal run shall be allowed and all bends and offsets shall be avoided as much as possible. Conduits shall be supported at 1,500 mm intervals maximum.

#### Conduit Boxes & Fittings

Provide conduit boxes for pulling and splicing wires and outlet boxes for installation of wiring devices.

As a rule, provide junction boxes or pull boxes in all runs greater than 30 metres in length, for horizontal runs. For ohter lengths, provide boxes as required for splices or pulling. Pull boxes shall be installed in inconspicuous but accessible locations.

Support boxes independently of conduits entering by means of bolts, red hangers or other suitable means.

Conduit boxes shall be installed plumb and securely fastened. They shall be set flush with the surface of the structure in which they are installed where conduits are run concealed.

All convenience and wall switch outlet boxes for concealed conduit work shall be deep, rectangular flush type boxes. Four-inch octagonal flush type boxes shall be used for all ceiling light outlets and shall be of the deep type where three or more conduits connect to a single box.

Floor mounted outiet boxes required shall be waterproof type with flush brass floor plate and brass bell nozzle.

All boxes shall be bainted with antirust red lead paint after installation. All conduits shall be fitted with approved standard galvanized bushing and locknuts where they enter cabinets and conduit boxes.

Junction and pull boxes of code gauge steel shall be provided as indicated or as required to facilitate the pulling of wires and cables.

# 1100.4 Method of Measurement

The work under this Item shall be measured either by lengths, pieces, pairs, lot and set actually placed and installed as shown on the approved Plans.

#### 1100.5 Basis of Payment

All works performed and measured and as provided for in the Bill of Quantitites shall be paid for at the Unit Bid or Contract Unit Price which payment shall constitute full compensation including labor, materials, tools and incidentals necessary to complete this Item.





Payment shall be made under :

Pay Item	Description	Unit of
Number		Measurement
(1)	RSC Conduit Pipe - mm dia.,	length
	with couplings	_
(2)	Locknut & Bushings	pairs
(3)	Condulet type	pieces
(4)	Conduit pipe elbow	pieces
(5)	Connector	pieces
(6)	Conduit clamp	pieces
(7)	PVC adapter	pieces
(8)	G.I. Wire G.A.# 14	kilos
(9)	Hacksaw Blade	pieces
(10)	PVC Tape 19 mm dia x 18 mm	Troils
(11)	Rubber Tape 19 mm dia x 227 g	rolls
(12)	PVC Solvent Cement @ 400 cc	cans
(13)	PVC End Ball	pieces
(14)	Octagonal junction boxes	pieces
(15)	Utility Boxes	pieces
(16)	Metal Pull Box	pieces
(17)	Square Box	Pieces
(18)	Telephone Cabinet	set
(19)	Reinforced Concrete Pedestal	
, ,	Pole	lot
(20)	Red Lead Point	iot
(21)	Weatherhead with type "F"	
	condulet	pieces
(22)	Grounding Rod copperweld	
	20 mm dia x 3 m	length
(23)	Apitong or Approved equal	
, .	creosoted wood pole	pieces
(24)	Anchor Rod - mm dia	pieces
(25)	Anchor Log - mm dia	pieces
(26)	Powerload Studs with nuts	Pieces

#### 1100.6 General Specifications

The work to be done under this division of specifications consists of the fabrication, furnishing, delivery and installation; complete in all details of the electrical work, at the subject premises and all work materials incidental to the proper completion of the installation, except those portions of the work which are expressly stated to be done by other fields. All works shall be done in accordance with the rules and regulations and with the specifications.

#### 1100.7 Specifications on:

1. Lighting fixtures and lamp

All lighting fixtures and lamps are as specified and listed on lighting fixture schedule.





For flourescent lamp , it shall be 40-watt rapid start cool-white. All flourescent ballast shall be 230 volt, high power factor, of good quality materials and approved by the Bureau of Product Standards (BPS).

Material Requirements 2.

All materials to be used shall conform to the BPS specification.

Construction Requirements 3

All grounding system installation shall be executed in accordance with the approved plans.

Grounding system shall include building perimeter ground wires, ground rods, clamps, connectors, ground wells amd ground wire taps as shown in the approved design.

# 1100.8 Auxiliary Systems

All auxiliary systems such as telephone and intercom system, time clock system, fire alarm system and public address/nurse's call/paging system installations shall be done in accordance with the approved design.

All materials to be used shall conform to the Bureau of Product Standards (BPS) specifications.

1100.9 Important requirement regarding supervision of the work and submission of certificate of completion.

All wiring installation herein shall be done under the direct supervision of a licensed Electrical Engineer at the expense of the Contractor. The contractor shall submit the certificate of completion duly approved by the owner's representative.

# 1100.10 Test and guarantee

Upon completion of the electrical construction work, the contractor shall provide all test equipment and personnel and to submit written copies of all test results.

The contractor shall guarantee the electrical installation are done and in accordance with the approved plans and specifications. The contractor shall guarantee that the electrical systems are free from all grounds and from all defective workmanship and materials and will remain so for a period of one year from date and acceptance of works. Any defect shall be remedied by the Contractor at his own expense.





### **1101 Wires and Wiring Devices**

# ITEM 1101 - WIRES AND WIRING DEVICES

#### 1101.1 Description

This Item shall consist of the furnishing and installation of all wires and wiring devices consisting of electric wires and cables, wall switches, convenience receptacles, heavy duty receptables and other devices shown on the approved Plans but not mentioned in these specifications.

# 1101.2 Material Requirements

Wires and cables shall be of the approved type meeting all the requirements of the Philippine Electrical Code and bearing the PSA mark

Unless specified or indicated otherwise, all power and lighting conductors shall be insulated for 600 volts.

All wires shall be copper, soft drawn and annealed, smooth and of cylindrical form and shall be centrally located inside the insulation.

All wiring devices shall be standard products of reputable electrical manufacturers. Wall switches shall be rated at least 10A, 250 volts and shall be spring operated, flush, tumbler type. Duplex convenience receptacies shall be rated at least 15A, 250 volts, flush, parallel siots. Single heavy duty receptacles shall be rated at least 20A, 250 volts. 3-wire, flush, polarized type.

# 1101.3 Construction Requirements

Conductors or wires shall not be drawn in conduits until after the cement plaster is dry and the conduits are thoroughly cleaned and free from dirt and moisture. In drawing wires into conduits, sufficient stack shall be allowed to permit easy connections for dixtures, switches, receptacles and other wiring devices without the use of additional splices.

All conductors of convenience outlets and lighting branch circuit homeruns shall be wired with a minimum of 3.5 mm in size. Circuit homeruns to panelboards shall not be smaller than 3.5 mm but all homeruns to panelboard more than 30 meters shall not be smaller than 5.5 mm. No conductor shall be less than 2 mm in size.

All wires of 14mm and larger in size shall be connected to panels and apparatus by means of approved type lugs or connectors of the solderless type, sufficiently large enough to enclose all strands of the conductors and securely fastened. They shall not loosen under vibration of normal strain.

All joints, taps and splices on wires larger than 14 mm shall be made of suitable solderless connectors of the approved type and size. They shall be taped with rubber and PVC tapes providing insulation not less than that of the conductors.

No splices or joints shall be permitted in either feeder or branch conductors except within outlet boxes or accessible junction boxes or pull boxes. All joints in branch circuit wiring shall be made mechanically and elactrically secured by approved splicing devices and taped with rubber and PVC tapes in a manner which will make their insulation as that of the conductor.

All wall switches and receptacles shall be litted with standard bakelite face plate covers. Device plates for flush mounting shall be installed with all four edges in continuous contact with finished wall surfaces without the use of coiled wire or similar devices. Plaster fillings will not be permitted.





# 1101.5 Basis of Payment

All work performed and measured and as provided for in this Bid of Quantities shall be paid for at the Unit Bid or Contract Unit Price which payment shall constitute full compensation including labor, materials, tools and incidentals necessary to complete this Item.

Payment shall be made under:

Pay Item Number	Description	Unit of Measurement
(1) (2)	Electric Wire Single pole tumbler switch	meter of rolls pieces
(3)	Two-gang tumbler switch	nieces
(4)	Three-gang tumbler switch	Dieces
(5)	Three-way tumbler switch	Dieces
(6)	Duplex Convenience receptacles	set
(7)	Heavy Duty Convenience receptacles	set
(8)	Standard Telephone outlet bakelite cover with 9.52 center hole	pieces
(9)	Window type air conditioning outlet 3-prong polarized type	pieces
(10)	Bare copper wire	matore
(11)	Grounding clamps for electric wires	pieces
(12)	Messenger wire	motore
(13)	Guy wire	metere
(14)	Vibrating Bell	set
(15)	Traffic Light Control Panel	Set
(16)	Traffic Light metal enclosures complete with red and green light provided with reflectors and 152 mm diameter vibrating bell	set





## 1102 Power Load Center, Switch Gear and Panel Boards

# TEM 1102 - POWER LOAD CENTER, SWITCHGEAR AND PANELBOARDS

# 1102.1 Description

This Item shall consist of the furnishing and installation of the power load center unit substation or low voltage switchgear and distribution panelboards at the location shown or the approved Plans complete with transformer, circuit breakers, cabinets and all accessories, completely wired and ready for service.

# 1102.2 Material Requirements

All materials shall be brand new and shall be of the approved type. It shall conform with the requirements of the Philippine Electrical Code and shall bear the Philippine Standard Agency (PSA) mark.

# Power Load Center Unit Substation

The Contractor shall turnish and install an indoor-type Power Load Center UNit Substation at the location shown on the approved Plans if required. It shall be totally metal-enclosed, dead front and shall consist of the following coordinated component parts:

# High Voltage Primary Section:

High voltage primary incoming line section consisting of the following parts and related accessories:

- (a) One (1) Air-filled Interrupter Switch, 2-position (open-close) installed in a suitable air filled metal enclosure and shall have sufficient interrupting capacity to carry the electrical load. It shall be provided with key interlock with the cubicle for the power fuses to prevent access to the fuses unless the switch is open.
- (b) Three (3)-power fuses mounted in separate compartments within the switch housing and accessible by a binged door.
- (c) One 1) set of high voltage potheads or 3-conductor cables or three single conductor cables.
- (d) Lightning arresters shall be installed at the high voltage cubicle if required.

Items (a) and (b) above could be substituted with a power circuit breaker with the correct rating and capacity.

#### Transformer Section

The transformer section shall consist of a power transformer with ratings and capacities as shown on the plans. It shall be oil liquid-filled non-flammable type and designed in accordance with the latest applicable standards.

The transformer shall be provided with four (4 approximately 2 1/2 % rated KVA taps on the primary winding in most cases one (1) above and three (3) below rated primary voltage and shall be changed by means of externally gang-operated manual tap changer only when the transformer is de-energized. Tap changing under load is acceptable if transformer has been so designed.

The following accessories shall be provided with the transformer, namely: drain valve, sampling device, filling, connection, oil liquid level





Low-Voltage Switchboard Section

The low-voltage switchboard shall be standard modular-unitized units, metal-built, dead front, safety type construction and shall consist of the following:

#### (a) Switchboard Housing

The housing shall be heavy gauge steel sheet, dead front type, gray enamel finish complete with frame supports, steel bracings, steel sheet panelboards, removable rear plates, copper busbars, and all other necessary accessories to insure sufficient mechanical strength and safety. It shall be provided with grounding bolts and clamps.

(b) Secondary Metering Section

The secondary metering section shall consist of one (1) ammeter, AC, indicating type; one (1) voltmeter, AC, indicating type, one (1) ammeter transfer switch for 3-phase; one (1) voltmeter transfer switch for 3-phase; and current transformers of suitable rating and capacity.

The above-mentioned instruments shall be installed in one compartment above the main breaker and shall be complete with all necessary accessories completely wired, ready for use.

# (c) Main Circuit Breaker

The main circuit breaker shall be draw-out type, manually or electrically operated as required with ratings and capacity as shown on the approved Plans.

The main breaker shall include insulated control switch if electrically operated, manual trip button, magnetic tripping devices, adjustable time overcurrent protection and instantaneous short circuit trip and ail necessary accessories to insure safe and efficient operation.

(d) Feeder Circuit Breakers

There shall be as many feeder breakers as are shown on the single line diagram or schematic riser diagram and schedule of loads and computations on the plans. The circuit brakers shall be drawout or molded case as required. The circuit breakers shall each have sufficient interrupting capacity and shall be manually operated complete with trip devices and all necessary accessories to insure safe and efficient operation. The number, ratings, capacities of the feeder branch circuit breakers shall be as shown on the approved Plans.

Circuit breakers shall each be of the indicating type, providing "ON" - "OFF" and "TRIP" positions of the operating handles and shall each be provided with nameplate for branch circuit designation. The circuit breaker shall be so designed that an overload or short on one pole automatically causes all poles to open.

Low-Voltage Switchgear

(For projects requiring low-voltage switchgear only)

The Contractor shall furnish and install a low-voltage switchgear at the location shown on the plans. It shall be metal-clad, dead front, free standing, safety type construction and shall have copper busbars of sufficient size, braced to resist allowable root mean square (RMS) symmetrical short circuit stresses, and all necessary accessories.

The low-voltage switchgear shall consist of the switchgear housing, secondary metering, main breaker and feeder branch circuit





breakers and all necessary accessories, completely wired, ready for service.

# Grounding System:

All non-current carrying metallic parts like conduits, cabinets and equipment frames shall be properly grounded in accordance with the PHilippine Electrical Code, latest edition.

The size of the ground rods and ground wires shall be as shown on the approved Plans. The ground resistance shall not be more than 5 ohms.

# Panelboards and Cabinets

Panelboards shall conform to the schedule of panelboards as shown on the approved Plans with respect to supply characteristics, rating of main lugs or main circuit breaker, number and ratings and capacities of branch circuit breakers.

Panelboards shall consist of a factory completed dead front assembly mounted in an enclosing flush type cabinet consisting of code gauge galvanized sheet steel box with thim and door. Each door shall be provided with catch lock and two(2) keys. Panelboards shall be provided with directories and shall be printed to indicate load served by each circuit.

Panelboard cabinets and trims shall be suitable for the type of mounting shown on the approved Plans. The inside and outside of panelboard cabinets and trims shall be factory painted with one rustproofing primer coat and two finish shop coats of pearl gray enamel paint.

Main and branch circuit breakers for panelboards shall have the rating, capacity and number of poles as shown on the approved Plans. Breakers shall be thermal magnetic type. Multiple breaker shall be of the common trip type having a single operating handle. For 50-ampere breaker or less, it may consist of single-pole breaker permanently assembled at the factory into a multi-pole unit.

# 1102.3 Construction Requirements

The Contractor shall install the Power Load Center Unit Substation or Low-Voltage Switchgear and Parielboards at the locations shown on the approved Plans.

Standard panels and cabinets shall be used and assembled on the job. All panels shall be of dead front construction furnished with trims for flush or surface mounting as required.

# 1102.4 Method of Measurement

The work under this item shall be measured either by set and pieces actually placed and installed as shown on the approved Plans.

#### 1102.5 Basis of Payment

All works performed and measured and as provided for in the Bill of Quantities shall be paid for at the Unit Bid or Contract Unit Price which payment shall constitute full compensation including labor, materials, tools and incidentals necessary to compelte this Item.





Payment shall be made under :

Pay Item Number	Description	Unit of Measurement
(1).	Panelboard (Circuit Breaker Type)	set
(2)	Panelboard (Safety Switch Type)	set
(3)	Low-Voltage Switchgear (LVS) complete with metering devices and accessories	set
(4)	Power Fuses	pièces
(5)	Lightning Arresters	pieces
(6)	Air Break Switch	set
(7)	Enclosed ACB NEMA Type I	set
(8)	Enclosed ACB NEMA Type 3R	set
(9)	Automatic Transfer Switch	set
(10)	Manual Transfer Switch without fuses	pieces
(11)	Motor Controller	set