

## *Section VI. Schedule of Requirements*

The delivery schedule expressed as weeks/months stipulates hereafter a delivery date which is the date of delivery to the project site.

Item No.	Description	Quantity	Unit	Delivered, Weeks/Months
1	<p><b>Additional Internet Connectivity for CDO Campus WIFI Services</b></p> <p>(Distribution to major buildings (8) see attached location map, INTERNET CONNECTION, 1Gbps, CIR/Transmission Rate, Direct Fiber Optic Line, reliability -99%, Contract period(12Months), Renewable annually based on the evaluation of Quality of Service(QoS),</p> <p>bundled with 14 usable Public IP</p> <p>10 units High Density WIFI 6 Indoor AP with Gigabit PoE Adaptor maximum of 1024 clients, 3 10/100/1000M Ethernet ports (The LAN1 Port supports PoE in, LAN3 Port supports LAN &amp; IoT module expansion with PoE out), compatible with existing Lifetime Free Cloud Management)</p> <p>5 units high-density WIFI 6(802.11ax) enterprise outdoor AP with Gigabit PoE Adaptor, IP68 rating, maximum of 1024 clients, 1 10/100/1000Base-T Ethernet uplink port (PoE) 1 SFP port, compatible with existing Lifetime Free Cloud Management)</p> <p>7 units Layer 2 Managed Switch 48 ports Switch (10/100/1000BASE-T ports + 4 * 1G/SFP ports compatible with existing Lifetime Free Cloud Management)</p> <p>1 unit Next-Gen Wireless Controller, 6 1000BASE-T ports, 2 1000BASE-T/1000BASE-X combo ports, 32 APs by default, compatible with existing Access Point.</p>	12	months	Sixty (60) calendar days
<b>***** Nothing Follows*****</b>				

bcl

4