

Section VI. Schedule of Requirements

The delivery schedule expressed as weeks/months stipulates hereafter a delivery date which is the date of delivery to the project site.

Item No.	Description	Quantity	Unit	Delivered, Weeks/Months
1	<p>ELEVATOR SYSTEM</p> <ul style="list-style-type: none"> - Rated Capacity: 500 - 800 kg/8 to 10 Persons - Travel Height: 8.0 Meters - Total Inner Shaft Size (mm) width (W); 1,800 ; Depth (D): 1,600 - No of Stops: 3 - Pit Depth (mm): 1,200 - Power Supply : 230 VAC, 3PH, 60 Hz - Speed: 1.0m/s - Clear Car Size (mm): Width (W): 1,100; Depth (D): 1,400 ; Height (H): 2,500 - Door Size (mm): Width (W) : 800 (W), Depth (H): 2,100 (H) - Inclusions : Arrival gong, 3-Way Intercom, Out of Service Switch, Car Call Cancellation, Anti-nuisance, Recall Control Panel, Reservation/ Independent Service, Emergency power Evacuation Control, Fire Service, Automatic Rescue Device, CCTV & Card Reader Interface, AVR w/ TVSS - Availability of Spare Parts: Readily - 2 weeks training and Familiarization 	1	lot	Two Hundred Ten (210) calendar days
***** Nothing Follows*****				

