

Section VI. Schedule of Requirements

The delivery schedule expressed as weeks/months stipulates hereafter a delivery date which is the date of delivery to the project site.

Item No.	Description	Quantity	Unit	Delivered, Weeks/Months
1	<p>ELEVATOR SYSTEM</p> <ul style="list-style-type: none"> - Rated Capacity: 450 kg/6 Persons - Travel Height: 8.0 Meters - Total Inner Shaft Size (mm): W; 2,100, D; 1,800 - No of Stops: 3 - Pit Depth (mm): 1,400 - Power Supply: 230 VAC, 3PH, 60 Hz - Speed: 1.0m/s - Clear Car Size (mm): W; 900, D; 1,350 , H; 2,300 - Door Size (mm): W; 750, Depth 2,100 (H) - Inclusions: Arrival Gong, 3-Way Intercom, Out of Service Switch, Car Call Cancellation, Anti-nuisance, Recall Control Panel, Reservation/ Independent Service, Emergency power Evacuation Control, Fire Service, Automatic Rescue Device, CCTV & Card Reader Interface, AVR w/ TVSS - Availability of Spare Parts: Readily Available from Service Center - 2 weeks Training and Familiarization 	1	lot	Two Hundred Ten (210) calendar days
***** Nothing Follows*****				

