

Section VI. Schedule of Requirements

The delivery schedule expressed as weeks/months stipulates hereafter a delivery date which is the date of delivery to the project site.

Item No.	Description	Qty.	Unit	Delivered, Weeks/Months
LOT 1: ICT EQUIPMENT (P1,500,000.00)				
1	<p>BRANDED ALL-IN-ONE COMPUTER</p> <p>23.8inch FHD, 1920x1080 resolution, Intel Core i7-13th Gen Processor, 16GB soDIMM DDR4, 512 GB M.2 2280 PCI-e Gen4 SSD + 1TB HDD 2.5-inch 5400 RPM/ NVIDIA GeForce dedicated with 2 GB of GDDR6, 802.11ax/ac/a/b/g/n, LAN 1G, Wi-Fi 6E and Bluetooth 5, Windows 11 Home SL; with USB Mouse, Keyboard and Integrated Built-in Webcam, Microphone and Speaker, includes AVR, includes delivery to USTP Alubijid</p>	20	units	Sixty (60) calendar days
LOT 2: ROUTING AND SWITCHING EQUIPMENT (P650,000.00)				
2	<p>ROUTING AND SWITCHING STANDARD LAB KIT</p> <p>A. Data Cabinet, W*D*H: 800*2000*800, High density vented mesh front door, high density vented mesh split rear door, 42U, Flat Packed, vented top, black9004, 2 units, 2U Cantilever Shelf, 2 Units rackmount 1 UPDU, 1 unit 4fan, 3 units Metal Cable Manager, 1 2U rackmount Drawer, 1 Unit Room Alert, 3W with temperature Sensor; CAT6 24 port Patch Panel (Unshielded, Loaded); CAT6 U/UTP Patch Cord (Unshielded, PVC, RED, 0.5m); CAT 6 UTP unshielded patch cord, PVC Blue 3m; CAT 4 pair U/UTP Cable (305m, unshielded, PVC, BLUE; CAT6 Keystone Jack (Unshielded, WHITE); 2 port faceplate, Shuttered (with label management 86x86mm); Back Box (86x86x42mm); Network Tools: 1pc. T3 Snapplug Crimping Tool, T3 CAT6 Snapplug connectors (200pcs) 1pc. T3 Punch Down tool 1pc T3 LAN Seeker Cable tested, 1pc Cable Stripper</p> <p>Main Router, Switch, and Access Point</p> <p>B. 3 units 1U rackmount, 10xGigabit Ethernet, SFP, USB 3.0, LCD, PoE out on port 10, 2x14GGz CPU, 1GB RAN, RouterOS L5 with SFP Module and Duplex Multimode Fiber Scale; 24 Gigabit port switch 2 x SFP+ cages in 1U rackmount case, Dual boot (RouterOS or SwitchOS); 802.11ax (Wifi 6) Dual-Radio PoE Access Point; Memory</p>	1	lot	Ninety (90) calendar days



	RT II Online 1KVA/900W 0.9PF with Internal battery, rack-tower convertible with bundled Rack Mount Kit (1:1) C. Delivery, Installation and User Trainings (Set-up Installation and Maintenance) Networking Training for 20pax, 24 Training Hours at USTP Alubijid			
***** Nothing Follows*****				