



UNIVERSITY OF SCIENCE AND TECHNOLOGY OF SOUTHERN PHILIPPINES
Alubijid | Balubal | Cagayan de Oro | Claveria | Jasaan | Oroquieta | Panaon | Villanueva

OFFICE OF THE BIDS AND AWARDS COMMITTEE I

BID FORM (BILL OF QUANTITIES)

NAME OF THE PROJECT : **PROPOSED COMPLETION OF SPORTS COMPLEX AND RESIDENCES (ISOLATION AND EVACUATION FACILITY) PHASE 2 (USTP-CDO) CY 2025**

APPROVED BUDGET OF CONTRACT : **TWELVE MILLION FIVE HUNDRED THOUSAND PESOS AND 00/100 (P12,500,000.00)**

BRIEF DESCRIPTION : **COMPLETION OF SPORTS COMPLEX AND RESIDENCES (ISOLATION AND EVACUATION FACILITY) PHASE 2 (USTP-CDO) CY 2025**

SOURCE OF FUND : **GAA CY 2025 THRU EARLY PROCUREMENT ACTIVITY FOR CY 2025**

CONTRACT DURATION : **ONE HUNDRED EIGHTY (180) CALENDAR DAYS**

ITEM NO.	DESCRIPTION/SPECIFICATIONS	QTY	UNIT	UNIT PRICE	AMOUNT
A. GENERAL REQUIREMENTS					
A.1.1(3)	Operation and Maintenance of Field Office for the Engineer	1.00	l.s.	P	P
B.3	Permits and Clearances	1.00	l.s.	P	P
B.9	Mobilization and Demobilization	1.00	l.s.	P	P
B.7	Occupational Safety and Health	1.00	l.s.	P	P
B.5	Project Billboard	2.00	each	P	P
B. EARTHWORKS					
803(1)a	Structure Excavation (common soil)	683.00	cu.m.	P	P
804(4)	Gravel Fill	68.30	cu.m.	P	P
C. SUBBASE COURSE AND BASE COURSE					
200	Aggregate Subbase Course, t= 150 mm	102.45	cu.m.	P	P
D. SURFACE COURSES					
311(1)a	Portland Cement Concrete Pavement (Unreinforced), t= 200mm thick, 14 days	136.60	sq.m.	P	P
E. STRUCTURAL WORKS					
902(1)b	Reinforcing Steel of Reinforced Concrete Structures (Deformed)	142.08	kgs	P	P
900(1)a1	Structural Concrete	6.00	cu.m.	P	P

ITEM NO.	DESCRIPTION/SPECIFICATIONS	QTY	UNIT	UNIT PRICE	AMOUNT
903(2)	Formworks	52.00	sq.m.	P	P
1047(2)a	Structural Steel (Decorative Louvers)	1,234.20	kg	P	P
F. ARCHITECTURAL WORKS					
1046(3)	Drywall Partition on Metal Studs and 6mm thick Ficemboard	55.20	sq.m.	P	P
1032(1)c	Painting Works (Fibercement Board)	110.40	sq.m.	P	P
1026(1)	Doors (steel door and jambs)	15.64	sq.m.	P	P
1012(7)	Glass and Glazing in Powder Coated Aluminim Frames combination of Fixed and Awning Windows	78.36	sq.m.	P	P
G. ELECTRICAL WORKS					
1002(16)a1	Generator Set, 250 KVA	1.00	l.s.	P	P
1002(15)	Transformer	1.00	l.s.	P	P
1002(17)	Automatic Transfer Switch	1.00	l.s.	P	P
1002(18)	Digital smart meter 3 phase	1.00	l.s.	P	P
1102(1)a	Main Circuit Breaker Panel, 630 AT CB, 3P, 630 AF, 42 KAIC	1.00	set	P	P
1102(1)b	Distribution Panel Board, 600 AT CB, 3P, 630 AF, 42 KAIC	1.00	set	P	P
H. MECHANICAL WORKS					
1200(13)a	Split-Type Air Conditioning Unit (Wall mounted, Floor mounted)	36.00	sets	P	P
1202(2)	Fire Pump	1.00	sets	P	P
1202(3)	Jockey Pump	1.00	set	P	P
1202(1)	Automatic Water Sprinkler System	1.00	l.s.	P	P
1202(a1)	Fire Extinguisher	21.00	pcs.	P	P
1202(5)	Fire Hose Cabinet	21.00	pcs.	P	P
I. ECE WORKS					
1106(1)	CCTV System (Dome Type, Revolving 360°, DVR)	14.00	pcs.	P	P
415(2)	Electronics Wall Outlets (Cable, HDMI, Single Data, Single Telephone)	10.00	pcs.	P	P
1105(20)	Structured Cabling System	1.00	l.s.	P	P
J. SITE DEVELOPMENT					

ITEM NO.	DESCRIPTION/SPECIFICATIONS	QTY	UNIT	UNIT PRICE	AMOUNT
807(1)	Paver Blocks including Gravel Bedding	105.00	sq.m.	P	P
TOTAL					P

Total Bid Price in Figure: _____

Total Bid Price in Words: _____

Name and Signature of Bidder: _____

All bid proposals must be sealed in envelopes properly labeled and submitted to this University on or before the deadline of submission of bids, **NOVEMBER 20, 2024, 01:30 P.M.** at the Procurement Services, 2nd Level Gymnasium Lobby, University of Science and Technology of Southern Philippines, C.M. Recto Ave., Lapasan Cagayan de Oro City.

The University of Science and Technology of Southern Philippines assumes no responsibility whatsoever to compensate or indemnify bidders for any expenses incurred in the preparation of the bid. The USTsP neither assumes any obligation for whatsoever losses that the bidders may incur in the preparation on their bids nor guarantee that an award will be made.


ATTY. JONATHAN S. OCHE
 BAC I Chairperson