UNIVERSITY OF SCIENCE AND TECHNOLOGY OF SOUTHERN PHILIPPINES
Alubijid | Balubal | Cagayan de Oro | Claveria | Jasaan | Oroquieta | Panaon | Villanueva

OFFICE OF THE BIDS AND AWARDS COMMITTEE I

BID FORM
(Bill of Quantities)

NAME OF THE PROJECT : **PROPOSED REPAIR AND IMPROVEMENT OF THE COLLEGE OF TECHNOLOGY BUILDING AT USTP-CDO CAMPUS CY 2026**

APPROVED BUDGET OF CONTRACT : **FIVE MILLION PESOS AND 00/100 (₱5,000,000.00) ONLY**

BRIEF DESCRIPTION : **REPAIR AND IMPROVEMENT OF THE COLLEGE OF TECHNOLOGY BUILDING AT USTP-CDO CAMPUS CY 2026**

SOURCE OF FUND : **IGF FY 2026**

CONTRACT DURATION : **ONE HUNDRED TWENTY (120) CALENDAR DAYS (ONE LOT)**

ITEM NO.	DESCRIPTION/SPECIFICATIONS	QTY	UNIT	UNIT PRICE	AMOUNT
A. GENERAL REQUIREMENTS					
A.1.1(16)	Operation & Maintenance of Field Office for the Engineer	1.00	l.s.	₱	₱
B.9	Mobilization and Demobilization	1.00	l.s.	₱	₱
B.7	Occupational Safety and Health	1.00	l.s.	₱	₱
B.5	Project Billboard	2.00	each	₱	₱
B. STRUCTURAL WORKS					
101(1)	Removal of Existing Concrete Topping/Structures and Obstructions	1.00	l.s.	₱	₱
1047(1)	Structural Steel, 5" HSS Pipe Sch. 40	1.00	l.s.	₱	₱
1047(2)a	Structural Steel, Trusses	5,725.30	kgs.	₱	₱
1047(2)b	Structural Steel, Purlins	5,474.70	kgs.	₱	₱
1047(7)a	Metal Structure Accessories, Anchor Bolts	15.60	kgs.	₱	₱
1047(7)b	Metal Structure Accessories, Sagrods	571.07	kgs.	₱	₱
1048(1)c	Metal Structure Accessories, Steel Plates	127.56	kgs.	₱	₱
C. REPAIR AND MAINTENANCE WORKS					
628	2" Cement Screed w/ Wiremesh & Hardener	1.00	l.s.	₱	₱
628(1)a	Waterproofing (Asphalt)	567.00	sq.m.	₱	₱
628(2)	Structural Concrete Injection and Crack Repair	1.00	l.s.	₱	₱
628(3)	Beam Steel Jacketing	1.00	l.s.	₱	₱
D. ARCHITECTURAL WORKS					
1016(1)b	Liquid Water Proofing (CEMENTITIOUS)	207.00	sq.m.	₱	₱
1014	Prepainted Metal Sheets (0.50m. Rib Type Long Span) Roofing	570.00	sq.m.	₱	₱

ITEM NO.	DESCRIPTION/SPECIFICATIONS	QTY	UNIT	UNIT PRICE	AMOUNT
1013(2)	Fabricated Metal Roofing Accessories (endwall flashing/end cap flashing)	50.00	l.m.	₱	₱
1013(2)c	Fabricated Metal Roofing Accessories (Gutter)	85.00	l.m.	₱	₱
1003(11)a1	Fascia (12 mm thick Fiber Cement on Metal Frames)	24.00	m.	₱	₱
1027(1)	Cement Plaster Finish 1/2"thk Plain Cement	240.00	sq.m.	₱	₱
1032(1)a	Painting Works (masonry/concrete)	240.00	sq.m.	₱	₱
E. PLUMBING WORKS					
1001(1)a5	PVC Pipes Vertical (Branch) and Horizontal	54.00	length	₱	₱
1001(10)	Polyvinyl Chloride (PVC) Fittings, Series 1000	1.00	l.s.	₱	₱
1001(11)	3/4" Overhead Tanks PVC Pipes Replacement	1.00	l.s.	₱	₱
1017(3)	Gutter/Deck Drain	8.00	sets	₱	₱
1001(5)	Catch Basin	9.00	sets	₱	₱
				TOTAL	₱

Total Bid Price in Figure:_____
Total Bid Price in Words:_____
Name and Signature of Bidder:_____

All bid proposals must be sealed in envelopes properly labeled and submitted to this University on or before the deadline of submission of bids, **DECEMBER 01, 2026 (TUESDAY), 09:30 A.M.** at the *Conference Room, Procurement Services Section, 2nd Floor DRER Gymnasium, USTP-CDO Campus, C.M. Recto Avenue, Lapasan, Cagayan de Oro City*.

The *University of Science and Technology of Southern Philippines – Cagayan de Oro (USTP-CDO) Campus* assumes no responsibility whatsoever to compensate or indemnify bidders for any expenses incurred in the preparation of the bid. The *USTP-CDO Campus* neither assumes any obligation for whatsoever losses that the bidders may incur in the preparation on their bids nor guarantee that an award will be made.

ATTY. JONATHAN S. OCHE
BAC I Chairperson